Northwestern

Restricted Access Utility Tunnel Entry Guidelines

Environmental Health and Safety

Table of Contents

I. Purpose 2
II. Scope 2
III. Definitions 2
IV. Responsibilities 2
V. Assessments 5
VI. Identification and Access 6
VII. General Safety Requirements 6
VIII. Restricted Access Utility Tunnel Entry 7
IX. Communication 9
X. Training 9
XI. Recordkeeping 9
XII. Regulatory Authority 10
XIII. Contact 10
Appendix A – Restricted Access Utility Tunnel Signage Example 11

vi. Maintain the database of utility tunnel assessments and provide them to applicable units and contractors as necessary and prior to entries.
vii. Review SOPs and other relevant documentation after each entry to ensure compliance with these guidelines.
viii. Review entry operations when there is reason to believe that the measures taken under these guidelines may not protect employees and revise the guidelines to correct deficiencies found to exist before subsequent entries are authorized. Examples of

xii. Assign the appropriate number of qualified individuals to maintain air monitoring equipment pursuant to the Northwestern Confined Spaces Program.

xiii. Notify EHS of changes to existing utility tunnels, the removal of utility tunnels, or the planning of new utility tunnels.

xiv.

E. Documented reassessments are required when there are changes to existing restricted access utility tunnels (e.g., new utilities, new hazards, configuration changes), including when non-restricted access utility tunnels may be reclassified as restricted access or confined spaces.

VI. Identification and Access

A. Restricted access utility tunnels must have appropriate danger signage posted at the minimum.

L. Adequate lighting must be established before commencing work.
M. Effective communication must be established and verified pursuant to Section IX – Communication.
N. Activities including, but not limited to, welding, drilling, cutting, and working with chemicals that produce potentially hazardous atmospheres or conditions (e.g., dust, fumes) require the use of ventilation equipment, specialized PPE, and other equipment or safety measures as necessary to ensure worker safety.
O. Tunnels that contain flammable gases (i.e., natural gas piping) present the potentiz(n)01 t (z(sn.s)-10.

ii. Completed (i.e., fully-signed) SOPs must be submitted to EHS for pre-entry review to ensure that those participating in entry operations are protected from utility tunnel hazards and compliance with these guidelines, which includes but is not limited to:
    a) Ensuring SOPs were completed properly,
    b) Ensuring all personnel involved signed the SOP, and
    c) Providing immediate feedback and guidance for any deficiencies, efficiencies, or opportunities for improvement identified.

IX. Communication

A. Effective two-way communication must be established, verified, and maintained during all restricted access utility tunnel entries:
    i. Between those inside the tunnel,
    ii. Between those inside the tunnel and those outside the tunnel, and
    iii. To summon emergency responders (e.g., fire department) in the event of an emergency.
B. Examples of acceptable forms of communication are:
    i. UHF portable radio,

iii. Maintain all completed (i.e., fully-signed) SOPs for at least 5 years.
iv. Maintain training records in myHR Learn for the duration of employment, plus 1 year.

B. Northwestern Units
i. Maintain air monitoring instrument records in accordance with the Northwestern Confined Spaces Program.
ii. Maintain and provide relevant system drawings, schematics, and other information to support tunnel entries.
iii. Submit all completed (i.e., fully-signed) SOPs to EHS at the completion of work.

C. Contractors
i. Submit all completed (i.e., fully-signed) SOPs to Northwestern at the completion of work.
ii. Maintain records (e.g., training records) as required by regulations.

XII. Regulatory Authority

Northwestern and its contractors will comply with the Occupational Safety and Health Administration's (OSHA) standards and any other applicable codes and standards, including:

Tunnel Assessments (SharePoint)
NFPA 101 – Life Safety Code
Northwestern Confined Spaces Program
Northwestern Contractor Safety Program
Northwestern Control of Hazardous Energy (Lockout/Tagout) Program
Northwestern Fall Protection Program
Northwestern Heat Illness Preve.7 (n)52 ( )10.6 (C)508 400.08 313.W.5 (o)-6.6 (u)13.D 86 >>BDC 0 g

FPq8NL-2s5 (L3-2.3 6-2e5.W6 i10.6 (o)-3.6 ((8)6g.5 L3-2.3 6)1